Talavera Suite Lantai 15 Jl. TB Simatupang 22 – 26 Jakarta Selatan, 12430 Telp. +62 21 29861000

SOLUSI BANGUN BETON

MIX PROPORTION DATA SHEET

(FORM : T2-MD2)

PROJECT : **Mess Taruna AAL**
LOCATION : **Tanjungsari**
CONTRACTOR : **PT Karen Nauli**

4071 /TC/QA/T2MD2/NA/IX/2024

PROJECT REQUIREMENT

Grade of Concrete	:	**K-300 (Fc 25MPa)**	
Slump	:	100	± 20 mm
W/Ct Ratio	:	0.55	

COMPOSITION FOR 1CuM (SSD Condition)

Nominal Water	:	180	Lt
Cement	:	325	kg
Fly Ash	:	-	

ADMIXTURE

Retarder (BWC)	:	0.2%	to 0.4%
Superplasticiser (BWC)	:		
HRWR (BWC)			

AGGREGATES

Fine Aggregates	:	850	kg
Coarse Aggregates	:	1,049	kg

TOTAL	:	2,406	kg
Density	:	2.406	T/CuM

REMARK FA0%

* PT Solusi Bangun Beton will not responsible for all quality matters if any material other than specified herewith is applied as substitution or addition to mix design at above.

As part of PT. Solusi Bangun Beton commitment to continous improvement, we reserve the right to change raw material sources or modify mix design in accordance with technical standard without notice

PORTEX - LOCKED - 2026-04-29