QA & QC ; R&D ; TECHNICAL CONCRETE & RAW MATERIAL DEPARTMENT

Head Office : Talavera Suite 17th Floor Jl.Let.Jend. TB. Simatupang No.22-26 Phone : +621-2129861000 Fax : +62-21 2986 0881

Central Laboratory: Jl. Rawa Sumur timur ujung Komplek JIEP- BLOK BB No.10A- Pulogadung

SOLUSI BANGUN BETON

MIX PROPORTION DATA SHEET

(FORM : T2-MD2)

PROJECT : Proyek Pura Office BSD

AREA PLANT : BP SERPONG

CONTRACTOR : PT PULAU INTAN BAJA PERKASA

No 10098/T2MD2/na/VII/2025

Material Price

PROJECT REQUIREMENT																	
Grade of Concrete	:		=	K-185 (Fc 15MPa)		K-350(Fc'30 Mpa)		K-350(Fc'30 Mpa)		K-350(Fc'30 Mpa)		K-425(Fc'35 Mpa)		K-425(Fc'35 Mpa)	
Slump	:		=	120	± 20 mm	120	± 20 mm	120	± 20 mm	180	± 20 mm	120	± 20 mm	120	± 20 mm
W/C Ratio	:		=	0.60		0.46		0.44		0.46		0.41		0.40	
CODE	:		=												
SAP CODE	:		=												
COMPOSITION FOR 1CuM (SSD Condition)															
Water	:		=	185	Kg	185	Kg	185	Kg	190	Kg	178	Kg	178	Kg
Cement	:		=	230	Kg	321	Kg	298	Kg	335	Kg	345	Kg	325	Kg
Semen Slag	:	SNI 6385:2016	=	77	Kg	80	Kg	80	Kg	82	Kg	86	Kg	75	Kg
Fly ash	:		=	-	Kg	-	Kg	39	Kg	-	Kg	-	Kg	40	Kg
Volume of Aggregates				0%		0%		9%		0%		0%		9%	
AGGREGATES															
Gravel-03	:	Split 5-25	=	1,030	Kg	1,019	Kg	1,028	Kg	1,032	Kg	1,030	Kg	1,025	Kg
Gravel-02	:	Split 10-20	=	-	Kg	-	Kg	-	Kg	-	Kg	-	Kg	-	Kg
Gravel-01	:	Split 5-10	=	-	Kg	-	Kg	-	Kg	-	Kg	-	Kg	-	Kg
Sand 1	:	Sand'	=	486	Kg	442	Kg	422	Kg	421	Kg	433	Kg	426	Kg
Sand 2	:	W.M.Sand	=	320	Kg	293	Kg	277	Kg	278	Kg	285	Kg	281	Kg
ADMIXTURE															
Retarder	:	Dar 36MR/Plastiment	=	1,550	ml	2,200	ml	2,050	ml	2,250	ml	2,300	ml	2,160	ml
Superplasticiser	:	Dar ADV	=	-	ml	1,100	ml	1,050	ml	1,150	ml		ml	-	ml
PCE	:	Viscocrete1826	=	-	ml	-	ml	-	ml	-	ml	1,550	ml	1,450	ml
TOTAL			=	2,328	Kg	2,340	Kg	2,329	Kg	2,338	Kg	2,357	Kg	2,350	Kg
Density			=	2.328	T/CuM	2.340	T/CuM	2.329	T/CuM	2.338	T/CuM	2.357	T/CuM	2.350	T/CuM
				1,026	M3	1,024	M3	1,024	M3	1,026	M3	1,027	M3	1,028	M3
REMARK				FA 10%		NFA		10%		NFA		NFA		FA 10%	

Jakarta, 6 Juli 2025

* PT Solusi Bangun Beton will not responsible for all quality matters if any material other than specified herewith is applied as substitution or addition to mix design at above.

As part of PT. Solusi Bangun Beton commitment to continous improvement, we reserve the right to change raw material sources or modify mix design in accordance with technical standard without notice

Form

16 June

FORTEX - LOCKED - 2026-04-30